

LINE TABLE - 8" PIPE

LINE	LENGTH	BEARING
L1	250.00	N38°01'47"W
L2	138.00	N72°01'47"W
L3	208.00	N55°41'47"W
L4	220.00	N27°01'47"W

SURVEYORS CERTIFICATE

STATE OF NEVADA)
) SS.
 COUNTY OF WASHOE)

I, STEVEN N BELL, BEING FIRST DULY SWORN, DEPOSE AND SAY THAT SITE INSPECTIONS HAVE BEEN MADE BY ME, OR UNDER MY SUPERVISION AND DIRECTION, ON JANUARY 5, 2010;
 THAT THE LOCATION OF EACH REFERENCE MONUMENT HAS BEEN VERIFIED BY SITE INSPECTION; THAT THE POINT OF DIVERSION AND PLACE OF USE SITES HAVE BEEN INSPECTED; THAT THIS MAP CONSISTING OF SHEETS NUMBERED FROM 1 TO 1, INCLUSIVE, HAS BEEN CORRECTLY DRAWN TO THE DESIGNATED SCALE FROM SURVEYING CALCULATION NOTES PREPARED BY ME, OR UNDER MY SUPERVISION AND DIRECTION, RELYING UPON ANALYSIS OF RECORDED SURVEY MAPS AND OTHER RECORDED SURVEYING DOCUMENTS, THAT THIS MAP TRULY AND CORRECTLY REPRESENTS THE PROPOSED LOCATION AND EXTENT OF THE WORKS USED TO DIVERT WATER FROM SANTA FE AND SHOSHONE CREEK, IN LANDER COUNTY, NEVADA BY YOUNG BROS. FOR POWER GENERATION (NON-CONSUMPTIVE).
 THAT THE PROPOSED POINT OF DIVERSION, THE APPROXIMATE LOCATION AND SIZE OF THE DIVERTING CHANNEL OR OTHER CONDUIT, ALL RESERVOIRS OR BASIN, THE LOCATION AND NAMES FOR ALL OTHER WORKS WHICH WILL CROSS OR CONNECT WITH THE PROPOSED WORKS, AND THE BOUNDARY OF ALL LANDS, SHOWING BY 40-ACRE SUBDIVISIONS THE AREAS PROPOSED TO BE SERVED, ARE FULLY AND CORRECTLY DESIGNATED THEREON.


YOUNG BROS.
 APPLICANT



Steven N. Bell
 STEVEN N. BELL
 STATE WATER RIGHT SURVEYOR No. 1137

SUBSCRIBED AND SWORN TO BEFORE ME
 THIS 13th DAY OF January, 2010.
 NOTARY PUBLIC IN AND FOR WASHOE COUNTY, NEVADA

Tammy Tubello
 NOTARY PUBLIC DATE 1-15-10



PROPOSED POINT OF DIVERSION

SANTA FE CREEK
 WITHIN THE SW1/4 NE1/4 OF SECTION 18, T16N, R44E MDB&M, AT A POINT FROM WHICH THE SOUTHEAST CORNER OF SECTION 17, T16N, R44E MDB&M, BEARS SOUTH 70°59'08" EAST, A DISTANCE OF 7967.39 FEET.


SHOSHONE CREEK
 WITHIN THE NE1/4 SW1/4 OF SECTION 18, T16N, R44E MDB&M, AT A POINT FROM WHICH THE SOUTHEAST CORNER OF SECTION 17, T16N, R44E MDB&M, BEARS SOUTH 78°00'15" E, A DISTANCE OF 8309.59 FEET.

PROPOSED POINT OF RETURN

WITHIN THE NE1/4 NE1/4 OF SECTION 21, T16N, R44E MDB&M, AT A POINT FROM WHICH THE NORTHEAST CORNER OF SAID SECTION 21 BEARS NORTH 73°10'00" EAST, A DISTANCE OF 350.00 FEET.

PROPOSED PLACE OF USE

WITHIN A PORTION OF THE NE1/4 NE1/4, OF SECTION 21, T16N, R44E MDB&M.




REFERENCE

DEPENDENT RESURVEY AND SURVEY OF TOWNSHIP 16 NORTH, RANGE 44 EAST, BY THE U.S.D.I. B.L.M. CADASTRAL SURVEY, DATED APRIL 22, 1981

BASIS OF BEARINGS

THE BASIS OF BEARINGS IS N 89°55' E ON THE NORTH LINE OF SECTION 21, T16N R44E MDB&M, AS SHOWN, PER REFERENCE.



Engineering & Planning
 280 Gregg Street, Suite 8
 Reno, Nevada 89502
 (775) 324-2663
 Fallon (775) 423-8701

STATE ENGINEER'S USE



MAP TO ACCOMPANY APPLICATION
 TO APPROPRIATE WATER
 FOR: POWER GENERATION
 (Non - Consumptive use)
 BY: YOUNG BROS.
 SOURCE: SANTA FE & SHOSHONE CREEK
 LANDER COUNTY NEVADA