DIVISION OF WATER RESOURCES
Carson City, Nevada
Profile prepared by:
Walter G. Reid, Civil Engr

LARGOMARSINO DITCH

Scale
1"=200'-Hor
1"=2' = Ver.



DIVERSION HEADGATE

Two 43" x 27" arch pipes, 18' long with paved invert sections and attached gates. Invert elevation is 4,365 ft. Rock dam in river, crest elevation 4,366 ft. or 4,367 ft.

ADDITIONAL WORK

Present ditch filled above Station 0+00 and flood wash diverted west to prevent present damage to ditch.

River 65.8
Ditch 65.4
Top Ditch (flume) 65.7

4365
4360
4355

Proposed Ditch Work

Ditch Section

(not to scale)

If found to be necessary two sections of ditch, approximately 150 ft. total length, will be lines.

0+00 5+00 10+00 15+00 20+00 25+00 30+00 35+00 40+00 45+00 50+00 55+00 60+00

KEUFFEL & ESSER CO. NEW YORK

TRADE STANDARD MARK 1000 DAR PAPER PROFILE PLATE A 4 X 20 PRINTED IN U.S.A.